



Cabidlanan, Nabunturan, Davao de Oro

Bid Number: B-25-0176
Date: 08/06/2025
Page: 1 of 3

ITEM NO.	QTY.	UNIT OF ISSUE	DESCRIPTION	APPROVED BUDGET		BID PRICES	
				Unit Price	Total Amount	Unit Price	Total Amount
1	1.0	lot	Supply & Installation of Tunnel Ventilation System for 300 sq.m Piggery TERMS & CONDITIONS 1.) Supply & Installation of Tunnel Ventilation System for 300 sq.m. Piggery and shall commence only upon receipt of Notice to Proceed; 2.) Scope of work to be undertaken shall conform with the Plans and Specification; 3.) All equipment needed in the implementation shall be provided by the supplier, to wit; a) Exhaust System – 4 units 50" fan, energy efficient single phase 220V, 1.5 - 2.0 HP Motor b) Pad cooling System – 2 units 2m x 4.5m x 15cm cooling pads in rectangular galvanized steel frame, 0.5 HP single phase dewatering submersible pump with 2m x 1.5m concrete tank. c) Mist Cooling System – 1HP single phase motor, 45 pcs. Super fine mister, uniform and drip-free solution, suitable for pulse activation with anti-drain valve. d) Side Wall Air Inlet Cover – 2 sets White Tarpaulin Canvas 2m x 30m Series 200 in Double shaft 24V Motor rated for 120-foot bottom rolling Vent. e) Automated control switch-15 Flexible Outputs-configured according to the field application; 6 Digital Inputs for water meter, fertilizer meter or pressure switch; 5 Analog Inputs for EC, pH, temperature and relative humidity. f) Advanced climate sensor-Modular features, control diverse modules	1,500,000.00	1,500,000.00		
			SUB-TOTAL		1,500,000.00		

Purpose: FOR THE USE OF PVO - ESTABLISHMENT OF SWINE MULTIPLIER AND TECHNOLOGY DEMONSTRATION - DUE TO NGA'S -
Delivery: DAVAO DE ORO FARM, PASIAN, MONKAYO, DAVAO DE ORO
Period of Delivery: 60 DAYS



Cabidlanan, Nabunturan, Davao de Oro

Bid Number: B-25-0176
Date: 08/06/2025
Page: 2 of 3

Purchase Request Number: 25-4400

ITEM NO.	QTY.	UNIT OF ISSUE	DESCRIPTION	APPROVED BUDGET		BID PRICES	
				Unit Price	Total Amount	Unit Price	Total Amount
			<p>and components (Air Vents, Fan and Pad, Misting, Air circulation and Lighting)</p> <p>g) Automatic Voltage Regulator (AVR)- 25 KVA Servo Motor type, 220V output</p> <p>4.) The supplier shall provide a minimum warranty of three (3) years against defective parts and equipment, excluding consumable parts;</p> <p>5.) The supplier shall offer free technical support services and must respond within 24 hours from the time of call in cases of system failure;</p> <p>6.) The supplier must provide after-sales support services, including a list of available technical personnel or service crew capable of performing immediate repair and maintenance services. An office or branch within Region XI must be available to ensure prompt response;</p> <p>7.) The supplier shall conduct the commissioning and testing of the entire system to ensure proper functionality and compliance with specifications;</p> <p>8.) The supplier shall provide free training to the designated end-users on operation, maintenance, and troubleshooting of the system;</p> <p>9.) The supplier shall assume full responsibility and accountability for the safety and execution of all site operations, including the installation methodology;</p> <p>10.) The Government shall not be held liable for any loss of or damage to the contractor's equipment, temporary works, or materials</p>				
			GRAND TOTAL		1,500,000.00		
Purpose: FOR THE USE OF PVO - ESTABLISHMENT OF SWINE MULTIPLIER AND TECHNOLOGY DEMONSTRATION - DUE TO NGA'S - Delivery: DAVAO DE ORO FARM, PASIAN, MONKAYO, DAVAO DE ORO Period of Delivery: 60 DAYS							



Cabidlanan, Nabunturan, Davao de Oro

Bid Number: B-25-0176
Date: 08/06/2025
Page: 3 of 3

ITEM NO.	QTY.	UNIT OF ISSUE	DESCRIPTION	APPROVED BUDGET		BID PRICES	
				Unit Price	Total Amount	Unit Price	Total Amount
			<p>stored at the project site;</p> <p>11.) The Government reserves the right to terminate or cancel the contract should the supplier fail to comply with any of the provisions set forth in these terms and conditions; and</p> <p>12.) Payment shall be made upon project completion, subject to evaluation and approval by the Provincial Agriculturist's Office and the Provincial Inspectorate Team.</p> <p>Site: Davao de Oro Farm, Pasian, Monkayo, Davao de Oro - Swine Multiplier Building, Pasian, Monkayo, Davao de Oro</p>				
			GRAND TOTAL		1,500,000.00		

Purpose: FOR THE USE OF PVO - ESTABLISHMENT OF SWINE MULTIPLIER AND TECHNOLOGY DEMONSTRATION - DUE TO NGA'S -
Delivery: DAVAO DE ORO FARM, PASIAN, MONKAYO, DAVAO DE ORO
Period of Delivery: 60 DAYS